

Test Report

Page 1 of 2

Client: Scientific Sanitation Solutions
Address: Unit 7,67 Regency Drive,Route 21 Corporate Park
Report no: 150532
Project: Scientific Sanitation Solutions

Date of report: 20 April 2023
Date accepted: 12 April 2023
Date completed: 20 April 2023
Date received: 12 April 2023

Lab no:		256844		
Date sampled:		11-Apr-23		
Aquatico sampled:		No		
Sample type:		Water		
Locality description:		Borehole Before		
Analyses		Unit	Method	
A	AQL pH @ 25°C	pH	ALM 20	8.06
A	AQL Electrical conductivity (EC) @ 25°C	mS/m	ALM 20	42.6
A	AQL Total dissolved solids (TDS)	mg/l	ALM 26	231
A	AQL Total Alkalinity	mg CaCO ₃ /l	ALM 01	172
A	AQL Chloride (Cl)	mg/l	ALM 02	26.8
A	AQL Sulphate (SO ₄)	mg/l	ALM 03	12.2
A	AQL Nitrate (NO ₃) as N	mg/l	ALM 06	1.94
A	AQL Total oxidised nitrogen as N	mg/l	ALM 06	1.94
A	AQL Ammonium (NH ₄) as N	mg/l	ALM 05	0.038
A	AQL Fluoride (F)	mg/l	ALM 08	<0.263
A	AQL Calcium (Ca)	mg/l	ALM 30	32.3
A	AQL Magnesium (Mg)	mg/l	ALM 30	16.6
A	AQL Sodium (Na)	mg/l	ALM 30	28.2
A	AQL Potassium (K)	mg/l	ALM 30	0.886
A	AQL Aluminium (Al)	mg/l	ALM 31	<0.002
A	AQL Iron (Fe)	mg/l	ALM 31	<0.004
A	AQL Manganese (Mn)	mg/l	ALM 31	<0.001
A	AQL Chromium (Cr)	mg/l	ALM 31	<0.003
A	AQL Copper (Cu)	mg/l	ALM 31	<0.002
A	AQL Nickel (Ni)	mg/l	ALM 31	<0.002
A	AQL Zinc (Zn)	mg/l	ALM 31	<0.002
A	AQL Cadmium (Cd)	mg/l	ALM 31	<0.002
A	AQL Lead (Pb)	mg/l	ALM 31	<0.004
A	AQL E.coli	CFU/100ml	ALM 40	<1
A	AQL Total coliform	CFU/100ml	ALM 40	<1

A = Accredited N = Non accredited Sub = Sub-contracted NR = Not requested RTF = Results to follow NATD = Not able to determine ATR = Alternative test report ; Results relate only to the items received and tested ; Results reported against the limit of detection; Results marked 'Non SANAS Accredited' in this report are not included in the SANAS Schedule of Accreditation for this laboratory; Uncertainty of measurement available on request for all methods included in the SANAS Schedule of Accreditation; The report shall not be reproduced except in full without approval of the laboratory

AQL = Aquatico Laboratories ; AQK = Aquatico Laboratories based in Kathu

M. Swanepoel
Technical Signatory

Test Report

Page 2 of 2

Client: Scientific Sanitation Solutions
Address: Unit 7,67 Regency Drive,Route 21 Corporate Park
Report no: 150532
Project: Scientific Sanitation Solutions

Date of report: 20 April 2023
Date accepted: 12 April 2023
Date completed: 20 April 2023
Date received: 12 April 2023

Lab no:			256844		
Date sampled:			11-Apr-23		
Aquatico sampled:			No		
Sample type:			Water		
Locality description:			Borehole Before		
Analyses			Unit	Method	
A	AQL	TotalViableCount	CFU/ml	ALM 43	3500
A	AQL	Turbidity	NTU	ALM 21	0.622
A	AQL	Total hardness	mg CaCO ₃ /l	ALM 26	149
A	AQL	Total organic carbon (TOC)	mg/l	ALM 63	1.52
A	AQL	Langelier Saturation Index	LSI	ALM 26	-0.19

A = Accredited N = Non accredited Sub = Sub-contracted NR = Not requested RTF = Results to follow NATD = Not able to determine ATR = Alternative test report ; Results relate only to the items received and tested ; Results reported against the limit of detection; Results marked 'Non SANAS Accredited' in this report are not included in the SANAS Schedule of Accreditation for this laboratory; Uncertainty of measurement available on request for all methods included in the SANAS Schedule of Accreditation; The report shall not be reproduced except in full without approval of the laboratory

Authenticated signature on first page

AQL = Aquatico Laboratories ; AQK = Aquatico Laboratories based in Kathu